

3-18
4-032210

15-109-2005-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1972

C NW SE /4 SEC. 12, 11, 32 W
1980 feet from S section line
1980 feet from E section line

Operator license# 5038

Lease: Swart C Well # 1

Operator: Robinson Oil Company

County: Logan 152.75

Address: 737 R.H. Garvey Building
Wichita, Kansas 67202

Well total depth 4700 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Quality Well Service License# 31925

Address: Sterling, Kansas 67579

Company to plug at: Hour: A.M. Day: 18 Month: March Year: 1997

Plugging proposal received from: Richard

Company: Quality Well Service Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order sand and common cement.

RECEIVED
KANSAS CORP COM
997 MAR 27 A 11:42
3-27-1997

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 18, Month: March, Year: 1997

Actual plugging report: 8 5/8" set at 258' w/150 sxs. 5 1/2" set at 4692' w/190 sxs. PBTD 4659'. Prod. Perfs 4108' - 4513'. Sanded back to 4050' w/5 sxs common cement on sand with bailer. Critical area control shots at 2500' - 2100' 1850' and free at 1615'. Mixed and pumped 170 sxs cement blend with hulls to 2500' w/500# P.S.I. Pulled casing to 300'. Mixed and pumped to circulate with 40 sxs cement blend. Pulled casing. Hole remained full. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

INVOICED

did not observe the plugging.

Carl Goodrow
(agent)

DATE APR 04 1997

INV. NO. 47859