

15-109-20063-00-00

P2gd. 12-11-84

6030829

API NUMBER 15-109-20,063-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SEW SEC. 18, T 11 S, R 32 NE

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Lease Name LENTIL Well # B-1

Operator License # 5181

County LOGAN 150.48

Operator: DONALD C. SLAWSON

Well Total Depth 4630 feet

Name & Address 200 DOUGLAS BLDG.

Conductor Pipe: Size _____ feet

WICHITA, KANSAS

Surface Casing: Size 8 5/8 feet 264'

67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CSG. PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: AM Day: 11 Month: 12 Year: 19 86

Plugging proposal received from Bill

(company name) KELSO CSG. (phone) _____

were: 8 5/8 SET @ 264' w/ 200SX. 4 1/2" SET @ 4327' PBD 4284' PERF.

4247-50' ORDER SAND & COM. CNT. SHOTS & PULL PIPE ORDER

200SX. ATL 65/35 po2 10% GEI 2% DICEL CNT. MIX. 6SX. HULLS. ALLIED CNT. CO.

WELLBROCK CNT. CO.

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:AM Day: 11 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBD TO 4200' w/ 4SX. COM. CNT. ON SAND

6SHOTS RECOVERED 1500' OF 4 1/2"

MIX & PUMP DOWN 8 5/8" 10 bbl slurry (20SX CNT. MIX) 6SX. HULLS

w/ 180SX. CNT. MIX. (15 bbl slurry) LOAD NOLE & SQUEEZE

MAX. PSI 300# CLOSE IN 150# Plug COMPLETE.

STATE CORPORATION COMMISSION

DEC 19 1986

1986

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (do not) observe this plugging.

Signed Carl Goodnow
(TECHNICIAN)

DATE 1-2-87

INV. NO. 15713