

15-109-20448-00-00

10-18-87

To: ⁶ 030980
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,448-00-00
SE NE NW SEC. 18, T 11 S, R 32 W/E
4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 06113

Lease Name Zerr Well # 1-18
County Logan 131.63

Operator: Landmark Oil Exploration Inc.
Name & Address 110 S. Main #510
Wichita, Kansas 67202

Well Total Depth 4050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco Inc. License Number 5147

Address Wichita, Kansas

Company to plug at: Hour: AM Day: 18 Month: October Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco (phone) _____

were: 8 5/8" set at 273' w/180 sks circ. hole with no less than 36 vis. mud with
no loss or gain of fluid. Spot cement plugs with drill pipe and balance with mud.
Order 200 sks 60/40 Poz 6% Gel 3% C C Cement Blend, 8 5/8" wiper plug. B. J. Titan.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30AM Day: 18 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Spot drill pipe and displace cement at 2575' w/25 sks
at 1600' w/100 sks + 1 sk Hulls.
at 325' w/40 sks
at 40' w/10 sks

cwc 15 sks rat hole
cwc 10 sks in mousehole

Remarks: Anhy 2566' - 96' Elev. 3061'
(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

INVOICED
DATE 12-4-87
INV. NO. 19123
10-18

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow