

8-22

15-109-20646-00-00

4- 090565

*zof*

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-109-20,646-00-00  
50'S.&110'W.  
SE NE SW \_\_\_\_\_ /4 SEC. 21, 11 S, 32 W  
1600 feet from S section line  
3080 feet from E section line

Operator license# 3447

Lease: Ziegler Well # 1-21

Operator: Ranken Energy Corporation

County: Logan 151.84

Address: 601 N. Kelly - Suite #103  
Edmond, OK 73003-4855

Well total depth 4672 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 20 Month: August Year: 1997

Plugging proposal received from: Syl Rome

Company: Abercrombie RTD, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel.  
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:15 A.M., Day: 22, Month: August, Year: 1997

Actual plugging report:

- 1st. Plug at 2550' w/25 sxs cement.
- 2nd. Plug at 1630' w/100 sxs cement.
- 3rd. Plug at 305' w/40 sxs cement.
- 4th. Plug at 40' w/10 sxs cement.
- 15 sxs in rathole.

Arbuckle - no - Anhydrite 2545'.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: 3028 GL

I did[  ] / did not[  ] observe the plugging.

Ed Schumacher  
(agent)

Form CP-2/3

**INVOICED**

DATE 8-29-97

INV. NO. 48885

*TD*

8-27-1997