

7-31

4-090563 15-109-20652-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-109-20,652-00-00

SW SE SE /4 SEC. 02, 11 S, 33 W
330 feet from S section line
990 feet from E section line

Operator license# 9860

Lease: Carrie "A" Well # 1

Operator: Castle Resources, Inc.

County: Logan 154.05

Address: 1200 East 27th St. - #C
Hays, Kansas 67601

Well total depth 4740 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 287 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: P.O. Box 763 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 29 Month: July Year: 1997

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc. Phone: -

Were: Order 195 sxs 60/40 posmix - 6% gel.

Spot all plugs through drill pipe with heavy mud between all plugs.

L-661-71-9

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 1:00 A.M., Day: 31, Month: July, Year: 1997

Actual plugging report:

1st. Plug at 2630' w/20 sxs cement.

2nd. Plug at 1610' w/100 sxs cement.

3rd. Plug at 340' w/40 sxs cement.

4th. Plug at 40' w/10 sxs cement.

15 sxs in rathole.

10 sxs in mousehole.

Arbuckle - no - Anhydrite 2621'.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3108 GL

I did [] / did not [X] observe the plugging.

Ed Schumacher
(agent)

Form CP-2/3

INVOICED

DATE 8-19-97

INV. NO. 48814