

6-090478

3-9

95R

15-109-20529-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,529-00-00

SW SW /4 SEC. 03, 11 S, 33 W  
660 feet from S section line  
460 feet from W section line

Operator license# 5011 Lease Trust Well # 1

Operator: Viking Resources, Inc. County Logan 152.75

Address: 105 S. Broadway, Suite 1040 Well total depth 4700 feet  
Wichita, Kansas 67202 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 387 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Mallard J V, Inc. License# 4958

Address: Wichita, Kansas

Company to plug at: Hour: PM Day: 05 Month: March Year: 1992

Plugging proposal received from: Julie

Company: Mallard J V, Inc. phone: (316)263-2243

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2630 feet with 20 sacks Rat hole: 15 sacks  
2nd plug @ 1630 feet " 100 " Mousehole: 10 sacks  
3rd plug @ 435 feet " 40 "  
4th plug @ 40 feet " wiper plug & 10 sks.

RECEIVED  
CORPORATION COMMISSION  
MAR 18 1992  
3-18-1992  
CONSERVATION

5th plug @        feet "  
Plugging Proposal Received by: Ed Schumacher P.I.R.T. III  
Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 4:00 PM, Day: 09, Month: March, Year: 1992

Actual plugging report: Hole reported plugged as above.  
Order 195 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3129 GL, Anhydrite depth: 2620 -        feet  
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: No  
Plugged through drill pipe: YES  
Did Not penetrate Arbuckle, cemented by Allied Cementing Company

I did [     ] / did not [ X ] observe the plugging. Ed Schumacher  
Ed Schumacher  
(agent)

4-8-92  
34903  
3-9