

4-061155

5-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20671-00-00
SW NE NE 1/4 SEC. 206, 11 S, 33 W
4290 feet from S section line
990 feet from E section line

Operator license# 3988 Lease: Dumler Well # Y-1
Operator: Slawson Exploration Co, Inc. County: Logan 155.03
Address: 200 N. Harvey - #1412 Well total depth 4770 feet
Oklahoma City, OK 73102 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 343 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A_X

Plugging contractor: Abercrombie, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: 5:00 P.M. Day: 27 Month: May Year: 1998

Plugging proposal received from: Tony Martin

Company: Abercrombie, Inc. Phone: -

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]


Completed: Hour 7:00 P.M., Day: 27, Month: May, Year: 1998

Actual plugging report:
1st. Plug at 2680' w/25 sxs. Anhydrite 2655' - 2685'.
2nd. Plug at 1675' w/100 sxs. Dakota 1369' - 1669'.
3rd. Plug at 400' w/40 sxs. Surface pipe - 343'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES _____ X _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO X Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____. Elevation: 3169 GL

I did / did not observe the plugging.

INVOICED


(agent)
Form CP-2/3

DATE JUN 03 1998
INV. NO. 50663

5-27