

2-27

74
R

4-071035

15-109-20549-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,549-00-00

SE NE NE /4 SEC. 09, 11 S, 33 W
900 feet from S section line
330 feet from E section line

Operator license# 5420 Lease Hecker well # 2

Operator: White & Ellis Drilling, Inc. County Logan

Address: P.O. Box 48848 Well total depth 4649 feet
Wichita, Kansas 67201 Conductor Pipe: 0 inch @ 0 feet
Michael L. Considine Surface pipe 8 5/8 Inch @ 333 feet

151.09

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: White & Ellis Drilling, Inc. License# 5420

Address: P.O. Box 48848 - Wichita, Kansas 67201-8448

Company to plug at: Hour: A.M. Day: 27 Month: February Year: 93

Plugging proposal received from: Bob Casper - Judy Steiben

Company: White & Ellis Drilling, Inc. Phone: 316-792-2424

Were: 8 5/8" 333' S.P. cwc. w/210 sx. 60/40 pozmix - 2% gel. - 3% c.c.
By Allied Cement. Miss. well - Elev. 3128' - Anhy 2614' - No circulation
problems. Mud condition 44 vis. - 8.9 wt. - 9.7 water loss.
Proposal 190 sx. 60/40 pozmix - 6% gel - 1 sx. flocele. Spots with drill
stem, circulate, heavy mud between all plugs. 25 sx. @ 2625' - 100 sx.
with flocele @ 1620' - 40 sx. @ 380' - 10 sx. @ 40'.
15 sx. in rat hole. (circulate)

RECEIVED
STATE CORPORATION COMMISSION

3-5-1993
MAR 05 1993

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 5:30A.M., Day: 27, Month: February, Year: 93

Actual plugging report: White and Ellis ordered 190 sx. 60/40 pozmix -
6% gel. - 1 sx. Flocele. Circulated hole, spotted and displaced all
cement with drill stem, heavy mud between all plugs.

1st. plug @ 2625' w/25 sx. cement.
2nd. plug @ 1620' w/100 sx. with 1 sx. flocele.
3rd. plug @ 380' w/40 sx. cement.
4th. plug @ 40' w/10 sx. cement.
15 sx. in Rathole. (circulate cement)

Remarks: By: Allied Cement.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 3128 GI

I did did not [X] observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE 3-5-93
37460
2-27