

15-109-20507-00-00

4-16

324

4 060186

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 109-20,507-00-00

NW NW NE , SEC. 9 , T 11 S, R 33 W

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Hecker Well # 1-9

Operator: Landmark Oil Exploration Inc.

County Logan 154.66

Name & Address 250 N. Water Suite 308  
Wichita, KS 67202

Well Total Depth 4759 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXX

Other well as hereinafter indicated

Plugging Contractor L.D.Drilling Inc. License Number 6039

Address Great Bend, KS

Company to plug at: Hour: 6:30AM Day: 16 Month: April Year: 1991

Plugging proposal received from Greg Davidson

(company name) L.D.Drilling Inc. (phone)

were: Order 190 sxs. 60/40 pos 6%gel 1/4# flocel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xxxxxxxx

Operations Completed: Hour: 6:30AM Day: 16 Month: April Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2640' with 25 sxs. Anhydrite 2623-2653'

2nd plug at 1630' with 100 sxs. Dakota 1330-1630'

3rd plug at 385' with 40 sxs. Surface pipe to 334'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

Remarks: Halliburton Cementing (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-29-91

INV. NO. 3170.1

Signed Herb Deines (TECHNICIAN)