

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21239-00-00
Spot: CNENENW Sec/Twnshp/Rge: 28-11S-31W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: GLASSMAN Well Number: 1
County: GOVE Total Vertical Depth: 4551 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

Conductor Pipe: Size feet: 3147.91
Surface Casing: Size 8.625 feet: 221 w/160 sxs cmt
Production: Size 4.5 feet: 4550 w/225 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/13/2002 10:00 AM
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 10% gel - 500# hulls.
D.V. at 2434' w/450 sxs.
Perfs at 4009' and 4390'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/13/2002 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing tied onto casing and pumped 50 sxs 60/40 pozmix with 400# hulls, followed by 10 sxs gel and 100# hulls.
Pumped an additional 75 sxs 60/40 pozmix with Max. P.S.I. 1500#. S.I.P. 1200#.
Tied onto backside and pumped 2 sxs with Max. P.S.I. 700#. S.I.P. 300#.
Job complete.


RECEIVED
3-15-2002
MAR 15 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #9303.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

MAR 14 2002

INVOICED
DATE Mar 19-02
INV. NO. 2002061537

Form CP-2/3

ERIC WADDELL COMPANY
NATOMA, KS 67651

28-11 -31W
NE NE NW

#1 GLASSMAN

site: 3-1/4 S & 6-1/2 W OF GRINNELL, KS city: GOVE API 15-063-21239
contr: ABERCROMBIE DRILLING, INC field: PENNY SE EXT (1/8 S)

geol: TRACY COOLEY

fr spd drlg card last
date 12/09/88 date 12/10/88 comp 12/20/88 issued 02/08/89 revised 02/08/89

ELV: 2907 KB LOG
tops.....depth/datum
ANH.....2414 +493
TOP.....3682 -775
HEEB.....3897 -990
LANS.....3944 -1037
BKC.....4220 -1313
MARM.....4251 -1344
MYR STA.....4385 -1478
MISS.....4520 -1613
RTD.....4551 -1644

IP status:
OIL, P 47 BO & 4 BWPD, MARM 4386-4390,
CSG: 8-5/8" 221 / 160 SX, 4-1/2" 4550 / 225 SX, DV
TOOL AT 2434 / 450 SX
NO CORES
DST (1) 3960-4007 (LANS C,D), / 60-45-60-45, REC 25'
OCM ISIP 845# FSIP 612# IFP 84# -84# FFP 84#
-84#
DST (2) 4007-4022 (LANS E,F), / 15-45-60-45, 1225'
GIP, REC 830' CLEAN GSY OIL, 120' MO, 80' SW ISIP
1256# FSIP 1130# IFP 95# -116# FFP 211# -369#
DST (3) 4156-4176 (LANS K), / 30-45-60-45, REC 180'
SW ISIP 1256# FSIP 1186# IFP 39# -68# FFP 98#
-118#

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)