

8 9-17 15-063-21284-00-00

To: 6 100396  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 15-063-21,284  
SE NW SE, SEC. 28, T. 11 S. R. 10 E. S. 10  
1650 feet from S section 10  
1650 feet from E section 10  
Lease Name Glassman Well #  
County Gove 152.75  
Well Total Depth 4700 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 278

RECEIVED  
NOV 20 1989  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

TECHNICIAN'S PLUGGING REPORT  
5123  
Operator License # \_\_\_\_\_  
Operator: Pickrell Drilling Co.  
Name & Address: 110 North Market  
Suite 205  
Wichita, Ks. 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor Pickrell Drilling Co. Inc. License Number 5123  
Address Wichita, Ks. 67202

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Doyle Folkers  
(company name) Pickrell Drilling (phone) \_\_\_\_\_

were: Spot plugs through drill pipe w/heavy mud between all plugs.  
1st plug at 2500' w/25 sks  
2nd plug at 1580' w/100 sks Rathole 15 sks  
3rd plug at 320' w/40 sks  
4th plug at 40' w/wiper plug and 10 sks.

Plugging Proposal Received by David K. Wann  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 10:30 AM Day: 17 Month: September Year: 19 89  
Order 190 sks 60/4 poz w/6% gel

ACTUAL PLUGGING REPORT  
and 2 sks celloflake/flowcel. Hole reported plugged as above.

Remarks: Elevation: 2981' GL, Anhydrite depth: 23493-2522'.  
Did not penetrate Arbuckle. Cemented by Allied.  
(If additional description is necessary, use BACK of this form.)

XXXXX (do not) observe this plugging.

INVOICED  
DATE 12-4-89  
INV. NO. 26561

Feb 5

Signed David K. Wann  
(TECHNICIAN)  
David K. Wann