

To: 6 041148
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-12,384

SE NE SE, SEC. 6, T 10 S, R 17 W/E

1650 feet from S section line

330 feet from E section line

Collins E-4

Lease Name Collins Well #

County Rooks 115.77

Well Total Depth 3562 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 151 w/100

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Operator: Davis Bro Oil Prod

Name & Address

105 S. Wyoming

Plainville, Ks. 67663

Abandoned Oil Well Gas Well Input Well x SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliuburton Cement License Number

Address Hays, Ks.

Company to plug at: Hour: 8:00AM Day: 19 Month: Mar Year: 19 90

Plugging proposal received from Chuck Arnold

(company name) David Bro (phone)

were: 4 1/2" casing set at 3460' w/275 sks. Top perf at 3353'. Perf anhy at 1400'

and base dakota at 800'. Ordered 50 sks common w/1/4" f.c. plus ordered 300 sks

65/35 poz 8% gel w/1/4" f.c. pus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:45PM Day: 19 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 50 sks common w/1/4" f.c. plus pumped in 4 1/2" casing

225 sks cement w/1/4" f.c. plus 3 sks hulls mixed in cement. Max 500# S.I. 200# psi.

Pumped in 8 5/8" casing 75 sks cement w/1/4" f.c. plus 2 sks hulls mixed in cement.

Max 300#. S.I. 100# psi.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 13 1990

INV. NO. 27840

Signed Dennis L. Hamel
Dennis L. Hamel (TECHNICIAN)