

7-26 15-163-30201-0000

To: 6 040935
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 10-10-66
SE SE SE, SEC. 7, T 10 S, R 17 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

_____ feet from S section line
_____ feet from E section line

Operator: Davis Bro Oil Prod Inc.
Name & Address: One Williams Center
S. 2000
Tulsa, Ok. 74172

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
9-16-88
CONSERVATION DIVISION
Wichita, Kansas

Lease Name Kleinschmidt BWell # 8
County _____ Rooks 116.58

Well Total Depth 3587 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 152' w/100 sks

Abandoned Oil Well _____ X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Ks.

Company to plug at: Hour: 8:30AM Day: 26 Month: July Year: 19 88

Plugging proposal received from Chuck Arnold

(company name) Davis Brothers (phone) _____

were: 4 1/2" casing set at 3585' w/275 sks. Top perf at 3468'. Sq at 1101' - 1130'
w/275 sks cement. Sq at 1900' - 1930' w/300 sks Common. Sq at 2088' - 2119'. Perf
casing at 800' w/3 holes. Ordered 250 sks 65/35 Poz 10% Gel w/1/4# Flocele plus 5 sks
Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 PM Day: 26 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 175 sks cement w/1/4# Flocele plus 3 sks

Hulls mixed in cement. Max 800# S.I. 500 Psi. Pumped in 8 5/8" casing 75 sks
cement w/1/4# Flocele plus 2 sks Hulls mixed in cement. Max 600# S:I. 300# Psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 9-20-88
INV. NO. 22290

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel