

6 040925

7-29 15-163-19398-0000

API NUMBER 15- 8-18-64

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NE , SEC. 7 , T 10 S, R 17 W

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Lease Name Kleinschmidt Well # B 1

Operator: Davis Bros. Oil Producers, Inc.

County Rooks 119.73

Name & Address One Williams Center,

Well Total Depth 3684 feet

Suite 2000

Conductor Pipe: Size _____ feet

Tulsa, Oklahoma 74172

Surface Casing: Size 8 5/8" feet 160

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor BJ Titan License Number _____

Address Hays, Kansas

Company to plug at: Hour: 10:00 pm Day: 29 Month: 7 Year: 19 88

Plugging proposal received from Chuck Arnold

(company name) Davis Bro (phone) _____

were: 4 1/2" csg set @ 3682' w/ 275 sx, Top perf @ 3682'; Sq. @ 1205' w/ 300 sx cmt. Perf @ 800' & 926'. Order 250 sx 65/35 poz, 10% gel w/ 1/4 Sx flo-cel, 6 sx hulls.

RECEIVED
STATE CORPORATION COMMISSION
9-16-88
SEP 16 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 2:15 pm Day: 29 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 150 sx cmt, w 1/4 sx flocele, 3 sx hulls, mixed in cmt. Max 800 #. Shut in 800# psi. Pumped in 8 5/8" casing 100 sx cmt, w 1/4 flocele, plus 3 sx hulls mixed in cmt. Max. 400# Shut in 200 # psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Date, ~~XXXXXX~~ observe this plugging.

DATE 9-20-88

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel

INV. NO. 22289