

To: **6 040933**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-26 15-163-00437-0002
2-22-66
API NUMBER 15-

SW SW SE SEC. 7, T 10 S, R 17 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

Lease Name Kleinschmidt Well # B-5

Operator: Davis Brothers Oil Prod Inc.
Name &
Address One Williams Center
S. 2000
Tulsa, Ok. 74172

County Rooks **120.54**
Well Total Depth 3709 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250' w/130

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Chuck Arnold

(company name) Davis Brothers (phone) _____

were: 4 1/2" casing set at 3709' w/275 sks. Top perf at 3459'. Fiberglass fish at 2160'. Hole in casing 2480'. Perf at 1400' and 800' anhy and Dakota.

Ordered 350 sks 65/35 Poa 10% Gel w/1/4# Flocele plus 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
9-16-88
SEP 16 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15AM Day: 26 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 175 sks cement w/1/4# Flocele plus 0 sks Hulls mixed in cement. Max 600#. S.I. 400# Psi. Pumped in 8 5/8" casing 75 sks cement w/1/4# Flocele plus 5 sks Hulls mixed in cement. Max 400# S.I. 300# Psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 9-20-88
INV. NO. 22285

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel