

3-19 15-163-30149-0001 70 R

6 041149

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-12,384
SE NE NE, SEC. 7, T 10 S, R 17 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5560

4920 feet from S section line
330 feet from E section line

Operator: David Bro Oil Prod
Name: One Williams Center, S-2000
Address: 105 S. Wyoming
Plainville, Ks. 67663
Tulsa, Okla 74172

Lease Name Kleinschmidt Well # B-4
County Rooks 115.54
Well Total Depth 3555 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 161 cwc

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number
Address Hays, Ks.

Company to plug at: Hour: 8:00 AM Day: 19 Month: Mar Year: 19 90

Plugging proposal received from Chuck Arnold

(company name) David Bro. (phone)

were: 5 1/2" casing set at 3554' w/150 sks. Top perf at 3412'. Perf anhy
at 1366' and base dakota at 776'.

Ordered 400 sks 65/35 poz 8% gel w/1/4# f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 10:45AM Day: 19 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 50 sks common w/1/4# f.c. plus pumped in 5 1/2" casing

325 sks cement w/1/4# f.c. plus 3 sks hulls mixed in cement. Max 300#. S.I. 100# psi.

Pumped in 8 5/8" casing 75 sks cement w/1/4# f.c. plus 2 sks hulls mixed in cement.
Max 500# S.I. 300# psi.

STATE CORPORATION COMMISSION
4-9-90
APR 09 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 13 1990

INV. NO. 22841
3-19

JLS

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel