

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19008-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 7-10S-17W  
4290 feet from S Section Line, <sup>1658</sup>~~2970~~ feet from E Section Line  
Lease/Unit Name: KLEINSCHMIDT Well Number: B-2  
County: ROOKS Total Vertical Depth: <sup>27KCL</sup>~~3500~~ 3650 feet

Operator License No.: <sup>6569</sup>~~3455~~  
Op Name: SCHMITT, CARMEN  
Address: 14 CIRCLE DRIVE  
BELOIT, KS 67420

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 175 W/125 SXS CMT  
Production: Size 4.5 feet: 3558 W/275 SXS CMT  
Liner: Size \_\_\_\_\_ feet:

12/20

118.63

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2000 8:00 AM  
Plug Co. License No.: <sup>6569</sup>~~3455~~ Plug Co. Name: SCHMITT, CARMEN  
Proposal Rcvd. from: CARMEN SCHMITT Company: SCHMITT, CARMEN Phone: (913) 738-3210

Proposed Plugging Method: Tubing fish in hole at 1175' - drilled out of casing.  
Orderd 200 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/20/2000 11:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 1075'. Spotted 110 sxs cement with 450# hulls,  
Mixed in cement. Circulated to surface.  
P.O.O.H. with tubing and squeezed 45 sxs cement to Max. P.S.I. 500#. S.I.P. 300#.  
R.U. cementers to 8 5/8" S.P.  
Squeezed surface pipe with 25 sxs cement with 25# hulls, pressured-up to 300#.  
Job complete.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

KANSAS CORPORATION COMMISSION

NOTICED

1/22/01

2001061350


JAN 19 2001 Form CP-2/3

1-19-01

CONSERVATION DIVISION

JAN 12 2001

11-301 MAP NO. \_\_\_\_\_ SEC. 7-10S-17W  
 STATE Kans COUNTY Rooks LOC. SE NW NE  
 OPER. Davis Brothers - Tulsa, Okla. FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL 2 FARM Kleinschmidt "B" FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 POOL Mt. Ayr ELEV. 2074 GR. 2076 DF 2079 KB  
 CONT. Transit Corp GEOL. Jack Cole  
 CO. \_\_\_\_\_  
 INT. 3700' Oil Test  
 F.R. 10-9-64 SPUD 10-10-64 COMP. 12-1-64  
 TD. 3650 FM. Cgl PBTD. \_\_\_\_\_



COMP  
RECORD

KC 3428-92 48 6500A

State Pot: P 55 BOPD & 26% wtr (Gr 35 deg)

8 5/8" @175 w/125 sx. 4 1/2" @3558 w/275 sx.

*Dade Inc.*

(KB Spl)		DST #1 (Tor-Lans) 3231-3344, Op 2 hrs,
Anh	1367 / 712	R 45' M, ISIP 931#/20", IFP 95#, FFP
B/Anh	1406 / 673	124#, FSIP 629#/20", RTD 3560 (Cgl), No
Top	3012 - 933	Log, 4 1/2" @3558 w/275 sx., MICT, Ran GRN
Hb	3228 -1149	Log, Pf 12/3489-92 (Lan-L zn), 500A, \$
Tor	3247 -1168	1d, \$ 3/4 BF (25% oil)/1st hr, \$ 1 BO/
Lan-A	3270 -1191	2nd hr, 3000A, \$ dn, \$ 6 3/4 BF (80% oil)
Lan-B	3304-21 -1225	/1st hr, \$ 4 1/2 BF (85% oil)/2nd hr, \$ 6
Lan-D	3325-29 -1246	1/3 BF (95% oil)/3rd hr (Gr 32 deg), \$
(Cont Below)		5 2/3 BF (95% oil)/4th hr, Pf 12/3468-71