

15-163-00992-0000

4-041791

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 9-1959

8-27

SE SW NW /4 SEC. 07, 10 S, 17 W
2970 feet from S section line
4290 feet from E section line

Operator license# 6569

Lease: Ross Well # C-1

Operator: Carmen Schmidt

County: Rooks 119.60

Address: P.O. Box 47
Great Bend, Kansas 67530

Well total depth 3680 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 155 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:30 A.M. Day 27 Month: August Year 1996

Plugging proposal received from: Curtis Hitchman

Company: Carmen Schmidt, Inc. Phone:

Were: 5 1/2" casing set at 3670' w/260 sxs cement. Perf. at 3509' - 3530'.
Perf salt at 1925' - Anhy. at 1440'. Squeeze at 925' with 350 sxs cement. Cement visible at surface.
Ordered 325 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 2:30 P.M., Day 27, Month: August, Year: 1996

Actual plugging report: R.I.H. with tubing to 3000'. Spotted 110 sxs cement with 300# hulls, pulled tubing to 1800'. Spotted 165 sxs cement with 300# hulls to circulate cement at surface. P.O.O.H. with tubing and squeezed casing with 50 sxs cement. Max. P.S.I. 600#. S.I.P. 300#.

RECEIVED
STATE CORPORATION COMMISSION
9-13-96
SEP 15 1996

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2102 GL

I did [X] / did not [] observe the plugging.

INVOICED

Remus L. Hamel
(agent)
Form CP-2/3

DATE 9-16-96
INV. NO. 46502