

4-020116

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,741-0000

NW NW NW /4 SEC. 09, 10 S, 17 W
4950 feet from S section line
4950 feet from E section line

Operator license# 6569

Lease: Fritts Well # 1

Operator: Carmen Schmitt *3/14*

County: Rooks *115.70*

Address: P.O. Box 47
Great Bend, Kansas 67530

Well total depth 3560 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 178 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Carmen Schmitt License# 6569

Address: P.O. Box 47 - Great Bend, Kansas 67530

Company to plug at: Hour: 9:00 A.M. Day: 14 Month: March Year: 2000

Plugging proposal received from: Curtis Hitschman

Company: Carmen Schmitt Phone: 316-793-2540

Were: Ordered out 265 sxs 60/40 pozmix - 10% gel - 600# hulls.
Prod. Perfs 3275' - 3474'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:00 P.M., Day: 14 Month: March, Year: 2000

Actual plugging report: 8 5/8" set at 178'. 4 1/2" set at 3560'.

Perforated casing at 1875' - 1350' - 800'.

Tied onto 4 1/2" and pumped 215 sxs cement - 400# hulls. Max. P.S.I. 600#. S.I.P. 300#.

Tied onto casing annulus and pumped 50 sxs cement w/100# hulls. S.I.P. 100#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING x Elevation: 2050 GL

I did [X] / did not [] observe the plugging.

INVOICED *100*

DATE 3/17/00

WVZ 061442

Jay Pfeifer
RECEIVED (agent)
STATE CORPORATION COMMISSION
3-17-2000
MAR 17 2000

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

(R)