

To: 6 041028
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # NA

Operator: Vincent J. Hrabe
Name & Address: % Northwestern Supply Co.
Box 1753
Hays, Ks. 67601

4-11
API NUMBER 15- 163-20,052-0001

SE NE NE, SEC. 18, T 10 S, R 17 W & E
feet from S section line
feet from E section line

Lease Name Plante Well # A-2

County Books 117.49

Well Total Depth 3615 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 167' w/135 sks

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☒ SWD Well ☐ D&A ☐
RTKCC

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: Day: 11 Month: April Year: 19 89

Plugging proposal received from Earl Thomason

(company name) Northwestern Supply (phone)

were: 4 1/2" casing set at 3613' w/275 sks. Top perf at 3493' - 3561'. Perf

anhy at 1425' and base Dakota at 850'. Ordered 300 sks 65/35 Poz 8% Gel w/1/4# F.C.
plus 8 sks Hulls.

5-10-89
MAY 10 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 5:45PM Day: 11 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 100 sks cement w/3 sks hulls; release wiper

plug, plus pumped add 150 sks cement w/1/4# f.c. plus 3 sks hulls mixed in cement. Max 600#

S.T. 300# psi. (Chased wiper plug to 1910' w/w.l.m. pressure picked up bottom plugged.

Pumped in 8 5/8" casing 50 sks cement w/1/4# f.c. plus 1 sk hulls mixed in cement. Max

300# S.T. 150# psi. (Pumped 95 bbls of total slurry in 4 1/2" casing.)

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(did not observe this plugging.)

DATE 5-11-89

INV. NO. 24773

Signed Dennis L. Hamel
(TECHNICIAN)

JUN 12 1989

AUG 08 1989

FEB 12 1990