

10-15 17 R

4-041419

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-20,066-0000
SE SE NE /4 SEC. 18, 10 S, 17 W
2970 feet from S section line
330 feet from E section line

Operator license# - Lease Plante A-5 well # A-5
Operator: State of Kansas Fee Fund County Rooks

Address: Kansas Corporation Comm. Well total depth 3626 feet
2301 E. 13th - Hays, Ks 67601 Conductor Pipe: 0 inch @ 0 feet
(Vincent J. Hrabe) Surface pipe 8 5/8 Inch @ 169 feet
w/135 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B-J Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 1 Month: October Year: 92

Plugging proposal received from: Dennis L. Hamel

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: 4 1/2" casing set @ 3624' w/275 sx. cement. Perf. 3483'-3575'.
Anhy. @ 1425'. Dakota @ 825'. W.L.M. 1775'.
Order 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 15, Month: October, Year: 92

Actual plugging report: R.I.H. with tubing to 2600'. Spot 150 sx. cem.
with 200# hulls. Pulled tubing to 1300'. Spot 50 sx. cement to circ.
at surface. P.O.O.H. with tubing. Squeezed 80 sx. cement with 200#
hulls. Max. 500#. S.I.P 200#. Hooked-up to 8 5/8" S.P. Pumped
in 50 sx. cement. Max. 600#. S.I.P. 200#.

RECEIVED
STATE CORPORATION COMMISSION
11-16-92
NOV 16 1992

Remarks: (Top of fluid 325') (Top capped w/ 2 sx. common cement)
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did[X] / did not[] observe the plugging. Dennis L. Hamel
(agent)