

10-14

R 14

4- 041415

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,065-00-00  
SE SW NE /4 SEC. 17, 10 S, 17 W  
2970 feet from S section line  
1650 feet from E section line

Operator license# - Lease Vohs well # E-2

Operator: State of Kansas Fee Fund County Rooks

Address: Kansas Corporation Comm. Well total depth 3636 feet  
2301 E. 13th - Hays, Ks 67601 Conductor Pipe: 0 inch @ 0 feet  
(Vincent J. Hrabe) Surface pipe 8 5/8 Inch @ 168 feet  
w/135 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B-J Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 14 Month: October Year: 92

Plugging proposal received from: Dennis L. Hamel

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: 5 1/2" casing set @ 3634' w/200 sx. cement. Perf. 3492'-3582'.  
Anhy. @ 1425'. Dakota @ 825'. W.L.M. 3602'.  
Order 350 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 5:00P.M., Day: 14, Month: October, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 150 sx.  
cement with 400# hulls. R.I.H. with perforators to perforate anhydrite  
at 1425' and base of Dakota @ 825'. Squeezed additional 150 sx. cement  
with 100# hulls Max. 600#. S.I.P 400#. Hooked-up to 8 5/8" S.P.  
and squeezed in 50 sx. cement. Max. 350#. S.I.P 200#.

Remarks: (Top of fluid 1175') (Top capped w/ 2 sx. common cement)  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL

I did[ X ] / did not[     ] observe the plugging.

Dennis L. Hamel DIVISION Kansas

HD

(agent)

NOV 16 1992