

To: 6 041025
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-28
API NUMBER 15-163-30292-0000
SE NE NW, SEC. 17, T 10 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

_____ feet from S section line

_____ feet from E section line

Lease Name Plante Well # A-3

Operator: KCC

County _____ Rooks _____

Name & Address FEE FUND

Well Total Depth EST 3600 feet

District #4

Conductor Pipe: Size _____ feet

Hays, Ks. 67601

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 8:00 A.M. Day: 28 Month: Feb Year: 19 89

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 4 1/2" casing set at NA /sks. Top perf at NA. Perf anhy at 1420'

and base Dakota at 850'.

Ordered 350 sks 60/40 Poz 8% Gel w/1/4# F.C. plus 4 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 28 Month: Feb. Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 3200'; Spotted 65 sks cement; pulled up to

2200'; sptd 65 sks cement; pulled up to 1420'; perforated casing at 1430'; sptd 50 sks

cement; pulled to 830' ; perf at 850'; sptd 35 sks cement. Cement circ. Pulled tubing

pumped add 60 sks cement in 4 1/2" casing.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I ~~did not~~ observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
4-19-89
APR 19 1989
SIGNED Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel