

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02980-00-01  
Spot: SWNWNW Sec/Twnshp/Rge: 20-8S-23W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HIGER Well #: 2  
County: GRAHAM Total Vertical Depth: 3730 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: 1889 200TH AVE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3729	0	w/unknown sxs cmt
SURF	8.625	200	0	w/unknown sxs cmt

121.23

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2009 10:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: RON'S OIL OPERATIONS, INC. Phone: (785) 421-2315

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Packer stuck in the hole at 3530'.  
Shot tubing off at 3495'.  
Operator requested all cement plug.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2009 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3494' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 2700' - pumped 150 sxs cement with 100# hulls.  
Pulled tubing to 1400' - pumped 135 sxs cement with 200# hulls - good circulation of cement.  
Pulled tubing out - tied onto 5 1/2" - squeezed with 15 sxs.  
Max. P.S.I. 400#. Shut in.  
Tied onto backside - pumped 2 sxs cement.  
Max. P.S.I. 200#. Shut in.

Perfs:

2-5-09  
2009061173

Remarks: ALLIED CEMENTING COMPANY-TICKET #34879.

Plugged through: TBG

District: 04

Signed Marvin Mills  
(TECHNICIAN) CM

PKT

20-8-23W  
SW NW NW

LEO J DREILING OIL CO #2 HIGER

Contr. MAST DRLG GRAHAM County

E 2188RB Comm. Comp. 10-1-57 IP 233 BOPD/LANS KC  
PERM PMP

Tops	Depth	Datum
ANH	1889	299
HEEB	3485	-1297
TOR	3510	-1322
LANS	3523	-1335
TD	3730	-1512

Casing  
8" 200  
5" 3729

DST 3668-3700/1/2 HR, 1560' GAS  
570' OIL, BHP 320#

PERF 3675-85: ACID 3000: SWB  
15 BOPH

HIGER POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS