

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20578-00-00
Spot: NWSW Sec/Twnshp/Rge: 2-19S-5W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: WILLIAMS BOB Well #: 1
County: MCPHERSON Total Vertical Depth: 1151 feet

Operator License No.: 32081
Op Name: SMOKEY VALLEY RESOURCES, INC.
Address: PO BOX 209
DEXTER, KS 67038

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1150	550	75 SX
SURF	7	204		100 SX

35

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/06/2009 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/06/2009 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 900' AND CAP WITH 4 SX'S CEMENT, CUT 4.5" CASING @ 551' AND PULL TO 400' AND CIRCULATE CEMENT TO SURFACE. PULL CASING ON OUT AND TOP OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
958	968		

2-5-09
2009061175

KANSAS CORPORATION COMMISSION
JAN 28 2009

Remarks: 60-40 POZ 4% GEL. COPELAND TICKET #C-33227. USED 160 SX'S TOTAL.

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

PKG