

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22123-00-00
Spot: E2SENV Sec/Twnshp/Rge: 30-29S-9W
3300 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HENNING Well #: 1
County: KINGMAN Total Vertical Depth: 2561 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: 10286 SW 170TH AVE
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2557	1410	125 SX
SURF	8.625	213		225 SX
T1	2.375	2460		

83.23

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/18/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50 FT ABOVE PERFS. CAP WITH 4 SKS OF CMT. RECOVER CASING .35 SKS 1400, 35 SKS 950', CIRC CMT FROM 260-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/18/2008 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 2390', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1410, WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 50 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 260', WHERE CMT WAS CIRCD TO THE SURFACE.

Perfs:

Top	Bot	Thru	Comments
2446	2454		

2-5-09
2009061179

KANSAS CORPORATION COMMISSION
JAN 26 2009


Remarks: QUALITY OIL WELL CEMENTING 60/40/4% GEL

RECEIVED

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

PKT