

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20692-00-00

KCC  
SPOT  
PICKUP  
@ 1500

Spot: <sup>S2</sup> N2SESE Sec/Twnshp/Rge: 30-34S-14W  
810 feet from S Section Line, 660 feet from E Section Line  
Lease Name: Z - BAR CATTLE CO Well #: 1  
County: BARBER Total Vertical Depth: 5200 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String Size Depth (ft) Pulled (ft) Comments  
PROD 4.5 4897 912 WITH 125 SX CMT  
SURF 8.625 405 WITH 350 SX CMT

169 -

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/14/2009 12:45 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4730' & PUT 4 SX CMT ON TOP. PLUG AT 1020' WITH 12 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2009 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*CASING LEAKS @ 2023' & 672'. UNABLE TO GET CASING LOOSE WITH RIPPERS. HAD PUT WIRE LINE COMPANY TO SHOOT OFF 4 1/2" CASING. UNABLE TO GET BELOW 912'. SHOT OF CASING @ 912.\*\* SANDED BACK TO 4730' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LAID CASING DOWN & RAN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 910' WITH 12 SX GEL & 50 SX CMT WITH 50# HULLS. 2ND PLUG AT 420' WITH 50 SX CMT & 50# HULLS. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4780	4790		

2-5-09  
2009061180

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 21 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

JAN 16 2009  
MP

Signed

*Stephen J Pfeifer*  
(TECHNICIAN)