

4-020040

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-spud 4/9/37
SE SE SE /4 SEC. 12, 11 S, 17 W
330 feet from S section line
480 feet from E section line

Operator license# 5652
Operator: Mustang Oil & Gas Corp.
Address: 100 S. Main, Suite 300
Wichita, Kansas 67202

Lease: F. Cress Well # 1
County: Ellis
Well total depth 3295 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 1/2 Inch @ 978 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 5652

Address: 100 S. Main, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: Day: 15 Month: December Year: 1993

Plugging proposal received from: Al Hammersmith

Company: Mustang Oil & Gas Corp. Phone: 316-267-8011

Were: 16" conductor casing set @ 280' w/250 sx cmt, 10 1/2" surface casing set @ 978' w/400 sx cmt, 6" production casing set @ 3285' w/150 sx cmt; Bridgeplug set @ 2800'; Perforations @ 2928-3131'; Elevation: 1771' GL; T.D. 3295'; Anhydrite: 965';

Ordered 340 sx cmt 60/40 pozmix w/10% gel, w/800# hulls, w/18 sx gel

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 16:15, Day: 15, Month: December, Year: 1993

Actual plugging report: Knocked bridgeplug to 3115+'; Ran in hole with tubing to 3091'; pumped 135 sx cmt w/100# hulls down 10 1/2" surface casing, Max. pressure: 150#, No detectable end pressure; Spotted 18 sx gel, 50 sx cmt w/250# hulls through tubing into 6" production casing - balanced cmt; Pulled tubing to 1707'; Spotted 50 sx cmt w/200# hulls; Pulled tubing to 1029'; Spotted 100 sx cmt w/200# hulls, cement circ. to surface; Pulled remaining tubing out of hole; Squeezed 5 sx cmt w/50# hulls; Maximum pressure: 400#, End pressure: 400#. Completion time: 4:15pm.

Remarks: Allied Cementing performed the cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 1771 GL

I did[X] / did not[] observe the plugging.

12-30-93
395-98
 (agent)

12/21/1993