

6 070386

15-051-05171-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

JW-SE-SW, SEC. 30, T. 11 S, R. 17 W

330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5076
Operator: Walters Drly Co Inc
Name & Address: 100 S Main Street
Ste 420
Wichita, Kans. 67202

Lease Name Peavey Well # 6
County Ellis 119.28
Well Total Depth 3670 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 167

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co License Number _____
Address Russell, Kansas

Company to plug at: Hour: 9:30 AM Day: 28th Month: Aug Year: 19 85

Plugging proposal received from Walt Zimmerman

(company name) Walters Drly Co. Inc (phone) 316-792-4181

were: 8 5/8" 167' SP. CUC Cu/NH, 5 1/2" Csg Set @ 3670' 1/100 SK out.
Top of Perfs 3361' 5 1/2" squeezed @ 871' 1/200 SK out.

No Pipe Recovery, ELV. 2130' Only 1364.

Order 270 1/40 Formix Gel - Ca. cl., 20 Gel, 5 Skulls and 5 1/2" Plug.
with Pump truck Pump in Annulus and 5 1/2" Csg.

Plugging Proposal Received by Maurin Schmidt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20 PM Day: 28th Month: Aug Year: 19 85

ACTUAL PLUGGING REPORT Ordered 270 1/40 Formix Gel - Ca. cl., 20 Gel, 5 Skulls + 5 1/2" plug
Pumped in Annulus 75 SK out 1/4 SK Skulls, Max 400 Psig, Shut in 300 Psig,
Pumped in 5 1/2" Csg, 50 SK out 1/2 SK Skulls, 20 SK Gel, 400 Psig
1/2 SK Skulls, Released plug and 130 SK out, Max pressure
1000 Psig shut in @ 400 Psig
Cemented by Allied Cmt.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE SEP 10 1985 STATE CORPORATION COMMISSION 9-9-1985

INV. NO. 9986 OCT 0 1985

Signed Maurin Schmidt DOIC (TECHNICIAN) 9-5-85