

11-23 15-051-24573-00-00

6 070730

API NUMBER 15- 051-24,573

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION N/2 N/2 NE, SEC. 30, T 11 S, R 17 W/EXX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4950 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067 Lease Name Hadley Well # 1

Operator: DaMar Resources, Inc. County Ellis 115.38

Name & Address Box 70 Hays, Ks. 67601 Well Total Depth 3550 feet

Operator Dan Schippers Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 1188

Abandoned Oil Well Gas Well Input Well SWD Well U&A x

Other well as hereinafter indicated

Plugging Contractor Western Kansas Drilling License Number Tag 1188

Address Hays, Ks. 67601

Company to plug at: Hour: AM Day: 23 Month: Nov Year: 19 88

Plugging proposal received from Jim Manley

(company name) Western Kansas Drilling (phone)

were: 8 5/8" 1188' S.P. cwc w/400 sks 60/40 Poz 3% Gel 2% Cal Cl. By Haleo

Arb at 3462'; Elv. 1950'; Anhy 1221'; No circulation problems; Mud condition 44 vis;

9.8 weight; 10.8 water loss. Proposal 215 sks 60/40 Poz 6% Gel 2% Ca Cl and 8 5/8"

plug. Spot with drill stem; Circulate heavy mud between all plugs. 25 sks at 3420';

25 sks at 1200'; 100 sks at 625'; 40 sks at 240'; 10 sks at 40'; 15 sks rathole (cir).

Plugging Proposal Received by MJS (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 7:45 AM Day: 23 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Ordered 215 sks 60/40 Poz 6% Gel 3% Cal Cl and 8 5/8" plug.

Spotted with drill stem heavy mud between all plugs.

1st plug at 3420' w/25 sks cement; 2nd plug at 1200' w/25 sks cement; 3rd plug at

625' w/100 sks cement; 4th plug at 240' w/40 sks cement. 10 sks in rathole - circulate.

Cemented by Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE DEC 19 1988

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

INV. NO. 23385