

15-051-05298-00-00

10-29-53

5-4-87

6 170553

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE SW SW, SEC. 30, T. 11 S, R. 17 W/R

_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5076

Lease Name Peavey Well # 2

Operator: Walters Drilling Inc.

County Ellis 118.82

Name & Address 100 S. Main #420

Well Total Depth 3656 feet

Wichita, Kansas 67202

Conductor Pipe: Size 0 feet

Robert E. Walters

Surface Casing: Size 8 5/8" feet 182'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Box 31, 332 W. Wichita, Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 4th Month: May Year: 19 87

Plugging proposal received from Walt Zimmerman

(company name) Walters Drilling Inc. (phone) 316-792-4181

were: 8 5/8" 182' S.P. CWC w/100 sk cmt, 5 1/2" csg. set at 3654' w/125 sk cmt. D.V. tool at

1355' CWC w/250 sk. cmt. Perfs. at 3637', No pipe recovery. Proposal, 220 sk. 65/35 Pozmix

10% Gel 2% Additive, 5 sk. Hulls. Load and squeeze annulus with cement pressure to 300 Psig.

and shut in. 5 1/2" csg. squeezed so load and pressure with cement from top to bottom with

pump truck. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 P.M. Day: 4 Month: May Year: 19 87

ACTUAL PLUGGING REPORT Ordered 220 sk 65/35 Pozmix, 10% Gel 2% Additive and 5 sk. Hulls.

Pumped in with pump truck.

1. Pumped 5 sk. cement in annulus, max. pressure 300 Psig. Shut in @ 300 Psig.

2. Pumped in 5 1/2" csg. 10 sk cement, 4 sk Hulls and 185 sk cement w/1 sk Hulls mixed in.

Max pressure 1500 Psig. Shut in with 1500 Psig. Cemented by Allied Cmt. Russell

STATE CORPORATION COMMISSION

5-11-1987

Remarks: 5-6-87

(If additional description is necessary, use BACK of this form to observe this plugging.)

INVOICED

DATE 5-15-87

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

INV. NO. 16923