

2-4

4-061041

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-24,953-00-00
115'E.&15'S.of
SE NW SE /4 SEC. 35, 11 S, 17 W
1635 feet from S section line
1535 feet from E section line

Operator license# 9860

Lease Hall Well # 1

Operator: Castle Resources, Inc.

County: Ellis 123.46

Address: 1200 E. 27th Street - Suite #C
Hays, Kansas 67601

Well total depth 3799 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: VonFeldt Drilling, Inc. License# 9431

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:30 A.M. Day: 4 Month: February Year: 1997

Plugging proposal received from: Darrell Krier

Company: VonFeldt Drilling, Inc. Phone: _____

Were: Order 225 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
FEB 12 10 28 AM '97
2-12-1997

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:15 A.M., Day: 4, Month: February, Year: 1997

Actual plugging report: _____

1st. Plug at 3630' w/25 sxs. Anhydrite 1294' - 1333'.

2nd. Plug at 1310' w/25 sxs. Dakota 479' - 779'.

3rd. Plug at 800' w/100 sxs. Surface pipe 209'.

4th. Plug at 260' w/40 sxs. Arbuckle 3650'

5th. Plug at 40' w/10 sxs.

15 sxs in rathole. - 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD ___ BAD ___ Anhy.plug: YES X NO ___

Bottom plug(in place): YES X, CALC___, NO ___ Dakota plug: YES X, NO ___

Plugged through TUBING___, CASING___ Elevation: 2104 GL

I did [] / did not [X] observe the plugging.

[Signature]
(agent)

DK.

Form CP-2/3

NOV 01 1997
DATE 11 23 1997
NO. 47568
2-4