

9-9

4-041935

15-051-04910-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 10-15-46

NW SW NW /4 SEC. 35, 11 S, 17 W  
1650 feet from N section line  
400 feet from W section line

Operator license# 5447

Lease: Hall J Well # 3

Operator: OXY USA, Inc.

County: Ellis 118.20

Address: Drawer D  
Plainville, Kansas 67663

Well total depth 3637 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 1135 Feet  
W/450 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 9 Month: September Year 1997

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: 5 1/2" casing set at 3637' w/150 sxs cement.  
Perfs at 3553' - 3600'. W.L.M. 2746'. Squeeze at 2208' - 2600'.  
Ordered 375 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 100# hulls.

11-5-1997

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:30 P.M., Day: 9, Month: September, Year: 1997

Actual plugging report: R.I.H. with tubing at 2720'. Spotted 100 sxs cement with 200# hulls.  
Pulled to 1200' - spotted 80 sxs cement with 200# hulls. Circulated cement to surface.  
Squeezed 8 5/8" with 100 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING Elevation: G.L.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

NOV 06 1997

DATE

49447

NO. 9-9

JAN 09 1998