

15-051-03629-00-00

fox
K...
1

6 041210

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 8-28-43
NW NW SW, SEC. 35, T 11 S, R 17 W/E

2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30364

Lease Name Hall Ls. Well # 1
County Ellis

Operator: Resource Operations Inc.
Name & Address: Box 466
Chase, Ks. 67524

Well Total Depth 2945 feet
Conductor Pipe: Size feet
Surface Casing: Size 13 3/8 feet 87 cement NA

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated OWWO Replug

Plugging Contractor Allied Cementing License Number
Address Russell, Ks.

Company to plug at: Hour: 8:00 AM Day: 22 Month: Aug Year: 19 90

Plugging proposal received from Melvin Brady
(company name) Resource Oper Inc. (phone)

were: see below

STATE CORPORATION COMMISSION

SWD 1 1990
9-4-1990

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part Dennis Hamel
None

Operations Completed: Hour: 9:00 AM Day: 23 Month: August Year: 19 90

ACTUAL PLUGGING REPORT R. I. H. w/tubing to 2945 to clean out hole to replug: Spot 50 sks 65/35
poz 8% gel w/1/4# f.c. w/50 lbs. Hulls in cement; displaced w/14 bbls rotary mud:

Pull up tubing to 2600; spot add 40 sks of gel (90 bbls of gel mud); pull up tubing to
1400: Spot 25 sks cement displaced w/7 bbls mud, pulled up to 750. Spotted 10 sks gel,
25 bbls mud, followed w/80 sks cement at 750: PULLED up tubing to 150 and cir cement to
surf w/100 sks.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / observe this plugging.

D.S.

Signed Dennis L Hamel
(TECHNICIAN) Dennis Hamel