

15-051-24881-00-00

STATE CORPORATION COMMISSION

4-071128

11-9

11-15-1994

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,881-00-00
160'W.

SE NE NW /4 SEC. 29, 11 S, 19 W
990 feet from S section line
2150 feet from E section line

Operator license# 5184 Lease Solomon well # 1

Operator: Shields Oil Producers, Inc. County Ellis

Address: Shields Building Well total depth 3706 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
M.L. Ratts Surface pipe 8 5/8 Inch @ 264 feet

120.45

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Shields Drilling, Inc. License# -

Address: Shields Building, Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 7 Month: November Year: 94

Plugging proposal received from: Burton Beery

Company: Shields Drilling, Inc. Phone: 913-483-3141

Were: 8 5/8" - 264' S.P. cwc. w/60/40 pozmix - 2% gel - 3% c.c. By Allied Cement. Elv. 2119' - Anhy. 1463' - No circulation Problems. Mud condition 36 vis. - 8.7 wt. - 8.8 water loss - chlorides 3,000 at 3015'. Proposal 225 sxs. 60/40 pozmix - 6% gel - 1/4# flocele per sack. Pump in with pump truck, spot and displace all cement through drill pipe - heavy mud between all plugs. No ar buckle - 25 sxs. cmt. @ 1470' - 100 sxs @ 770' - 40 sxs. @ 300' - 10 sxs. @ 40' - 15 sxs. rathole (circ) - 10 sxs in mousehole (circ).

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:45A.M., Day: 7, Month: November, Year: 94

Actual plugging report: Shields ordered 225 sxs. 60/40 pozmix - 6% gel - 1/4# flocele per sack. Pumped in with pump truck, circulated hole - spotted and displaced all cement through drill pipe. Mud condition 36 vis. - 8.7 wt. - 8.8 water loss - heavy mud between all plugs. No ar buckle.

1st. plug at 1470' w/25 sxs. cement. 4th. plug at 40' w/10 sxs. cement.
2nd. plug at 770' w/100 sxs. cement. 15 sxs. in rathole (circulated)
3rd. plug at 300' w/40 sxs. cement. 10 sxs. in mousehole (circulated)

Remarks: Cemented by Allied Cement.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2119 GL

I did[] / did not[X] observe the plugging.

Marion J. Schmidt

(agent)

Form CP-2/3

12-5-94

41788

HO