

9-18 15-051-24688-00-00

6 070860

API NUMBER 15 051-24,688

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SW NW NE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE \_\_\_\_\_, SEC. 29, T 11 S, R 19 W/Ex

4260 feet from S section line  
2280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30110

Lease Name Solomon Well # 2

Operator: Western Investments Inc.

County Ellis 120.08

Name & Address Box 370

Well Total Depth 3695 feet

Hays, Kansas 67601

Conductor Pipe: Size 0 feet

Don E. Pratt

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A xx

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Ks. Drilling License Number \_\_\_\_\_

Address Hays, Ks. 67601

Company to plug at: Hour: AM Day: 18 Month: Sept Year: 19 90

Plugging proposal received from Jim Manley

(company name) Western Ks. Drilling (phone) \_\_\_\_\_

were: 8 5/8 - 211 ft. s.p. cwc w/125 sks 60/40 poz 2% gel 3% ca cl. By Halliburton

No Arb. Jim Manley Elv. 2105. Anhy 1431, no cir problems. Mud condition 42 vis. 9.8

weight 12 water loss. Proposal 215 sks 60/40 poz 6% gel 1 sk f.c. and wiper plug. Spot

with drill stem, circulate heavy mud between all plugs. 25 sks at 3570. 25 sks at 1440 w/25 sks

cement. 100 sks cement w/1 sk f.c. at 750 - 40 sks at 260 - 10 sks at 40 ft. 15 sks in rathole.

Cir. \_\_\_\_\_ Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:30AM Day: 18 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Western Ks. Drilling ordered 190 sks 60/40 poz 6% gel

3% ca cl. 1 sk f.c. and 8 5/8 plug. Spotted with drill stem, circ, heavy mud between all

plugs 1st plug at 1440 w/25 sks cement 2nd plug at 750 w/100 sks cement w/1 sk f.c.

3rd plug at 260 w/40 sks cement. 15 sks in ratgole (cir) By Halliburton Cement

SEP 26 1990  
9-26-1990

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-90

INV. NO. 294.73

JAN 10 1991  
Gib. S.

Signed Marion J. Schmidt (TECHNICIAN)  
Marion J. Schmidt