

10-8
4-071069 15-051-24857-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-24,857
100'E.
NW NE NW /4 SEC. 32, 11 S, 19 W
330 feet from S section line
1750 feet from E section line

Operator license# 6569 Lease Solomon well # A-1

Operator: Carmen Schmitt County Ellis

Address: 3111 10th Street #200 Well total depth 3740 feet
P.O. Box 47 Conductor Pipe: 0 inch @ 0 feet
Great Bend, Kansas 67530 Surface pipe 8 5/8 Inch @ 210 feet

121.55

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling - Allied Cement License#

Address: Wichita, Kansas 67202 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 8 Month: October Year: 93

Plugging proposal received from: Keith Vanpelt

Company: Murfin Drilling Phone:

Were: 8 5/8" - 210' S.P. cwc. w/135 sx. 60/40 pozmix - 2% gel -
3% c.c. By: Allied Cementing. Elev. 2093' - Anhy. 1445' - Arbuckle 3690'
No circ. problems - Mud condition 9.2 - Vis. 45 - Water loss 9.6 -
Chlorides 3500 @ 2895. Proposal 215 sx. 60/40 pozmix - 6% gel - 1/4#
F.C. Spot with drill stem - circulate hole - heavy mud between all plugs.
25 sx. @ 3690' - 25 sx. @ 1470' - 100 sx. @ 750' w/1 sx. F.C. - 40 sx.
@ 250' - 10 sx. @ 40' - 15 sx. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30A.M., Day: 8, Month: October, Year: 93

Actual plugging report: Murfin Drilling ordered 215 sx. 60/40 pozmix -
6% gel and 1 sx. F.C. Circulated hole - spotted and displaced all
cement through drill stem - heavy mud between all plugs.

- 1st. plug @ 3690' w/25 sx. cement.
- 2nd. plug @ 1470' w/25 sx. cement.
- 3rd. plug @ 750' w/100 sx. cement w/1 sx. F.C.
- 4th. plug @ 250' w/40 sx. cement.
- 5th. plug @ 40' w/10 sx. cement. - 15 sx. in Rathole (circulate)

Remarks: By: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[] / did not[X] observe the plugging.

Marion J. Schmidt
(agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1993
10-20-1993
CONSERVATION DIVISION
Wichita, Kansas

10-22-93

39022

10-8

HO.