

8-12 4-110067

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-25,008-0000

NE SE SW NW / 4 SEC. 32 , 11 S , 19 W
3010 feet from S section line
4030 feet from E section line

Operator license# 32034 Lease: Terry Solomon Well # 32-2

Operator: Hal C. Porter County: Ellis

Address: 10004 W. 20th St. North
Wichita, Kansas 67212
Well total depth 3740 ^{121.55} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8⁵/₈ Inch @ 219 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 12 Month: August Year: 1999

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company Phone: 316-267-3241

Were: Plug according to Rules & Regulations set forth by the Kansas Corporation Commission.

Plugging Proposal Received by: Roger Moses
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 9:45 P.M. , Day: 12 , Month: August , Year: 1999

Actual plugging report: Set 8 5/8" S.P. at 219' w/150 sxs 60/40 pozmix - 3% c.c. and 2% gel.
1st. Plug at 3668' w/25 sxs - Arbuckle.
2nd. Plug at 1470' w/25 sxs - Anhydrite 1449' - 1489'.
3rd. Plug at 750' w/100 sxs - Dakota 450' - 750'.
4th. Plug at 270' w/40 sxs - Surface pipe.
5th. Plug at 40' w/10 sxs and 8 5/8" wiper plug. 15 sxs in rathole.
215 sxs total 60/40 pozmix - 6% gel and 1/4# flocele per sack.

8-30-1999

Remarks: Allied Cementing
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2100 GL

INVOICED did not [] observe the plugging.

Roger Moses
(agent)

DATE 8-31-99
INV. NO. 60449

Form CP-2/3