

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30705
Name: Younger Energy Company
Address 1: 453 S. Webb Rd., Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67207 + _____
Contact Person: Diane Rebstock
Phone: (316) 681-2542
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3917 Bottom: 3918 T.D. 3918
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 145-20,777 - 0000
Spot Description: _____
____ NW NW SW Sec. 35 Twp. 21 S. R. 15 East West
2,310 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pawnee
Lease Name: Keller Well #: 1
Date Well Completed: January 20, 1981
The plugging proposal was approved on: March 5, 2009 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: March 9, 2009
Plugging Completed: March 11, 2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	oil	Surface	8-5/8"	930'	none
		Production	4-1/2"	3916'	none

RECEIVED
APR 22 2009


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hit bridge @ 3173' +/- . Pumped 65 bbls mud and 50 sxs cement @ 3150'. Perforate 2 shots at 940'-941'. Pumped 150 sxs @ 965'. Tagged cement with tubing @ 620', pumped 30 sxs @ 600'. Pumped 20 sxs to squeeze annulus @ 150#. Topped off casing with 10 sxs to surface. Used total of 260 sxs 60/40 poz mix 4% gel.

Plugging Contractor License #: 7023 Name: Klima Well Service, Inc.
Address 1: P.O. Box 48 Address 2: _____
City: Great Bend State: KS Zip: 67530 + 0048
Phone: (620) 793-8888
Name of Party Responsible for Plugging Fees: Younger Energy Company
State of Kansas County, Sedgwick, ss.
Diane Rebstock Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Diane Rebstock Stacey L. Williamson
Notary



[Handwritten initials]