

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LARSON ENGINEERING, INC.
Address: 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561
Phone: (620) 653-7368 Operator License #: 3842

API Number: 15-167-23140 - 0000
Lease Name: POLCYN "A"
Well Number: 1

Type of Well: OIL Docket #: (Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): - C - W/2 - SE

The plugging proposal was approved on: 4/13/2009 (Date)

1320 Feet from [] North / [X] South Section Line

by: RICHARD WILLIAMS (KCC District Agent's Name)

1980 Feet from [X] East / [] West Section Line

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No

Sec. 10 Twp. 14 S. R. 15 [] East [X] West

Producing Formation(s): List All (If needed attach another sheet)

County: RUSSELL

GORHAM SAND Depth to Top: 3253 Bottom: 3256 T.D. 3256

Date Well Completed:

L-KC Depth to Top: 3042 Bottom: 3112 T.D.

Plugging Commenced: 4/20/2009

TOPEKA & TORONTO Depth to Top: 2740 Bottom: 2989 T.D.

Plugging Completed: 4/20/2009

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include GORHAM SAND, L-KC, and TOPEKA&TORONTO.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

PLUGGED W/ 230 SX 60-40 POZ W/ 4% GEL, 12 SX GEL & 500# HULLS AS FOLLOWS:

PUMPED 15 SX DOWN ANNULUS @ 300# & SI @ 300#. PUMPED DOWN CSG W/ 50 SX CMT W/ 200# HULLS, 12 SX GEL,

165 SX CMT W/ 300# HULLS, 700# MAX, SI W/ 500#. PLUGGING COMPLETE @ 3:00 PM, 4/20/2009.

KCC REPRESENTATIVE ON LOCATION: PAT STAAB

Name of Plugging Contractor: ALLIED CEMENTING CO., INC. License #: 99996 RECEIVED

Address: P.O. BOX 31 RUSSELL, KS 67665 APR 22 2009

Name of Party Responsible for Plugging Fees: LARSON ENGINEERING, INC. KCC WICHITA

State of KANSAS County, BARTON, ss.

CAROL LARSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carol Larson SECRETARY/TREASURER

(Address) 562 WEST STATE ROAD 4 OLMITZ, KS 67564-8561

SUBSCRIBED and SWORN TO before me this 21ST day of APRIL, 2009

DEBRA J. LUDWIG Notary Public - State of Kansas My Apct. Expires 5/5/2012

(Signature) Debra Ludwig My Commission Expires: 5/5/2012

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials 'PST' in the bottom right corner.