

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5663
Name: Hess Oil Company
Address 1: P. O. Box 1009
Address 2: _____
City: McPherson State: KS Zip: 67460 + 1009
Contact Person: Bryan Hess
Phone: (620) 241-4640
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4284' Bottom: _____ T.D. 4305'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 083-21,507-00-01
Spot Description: Approx.
SW NE SW Sec. 8 Twp. 21 S. R. 21 East West
1,550 Feet from North / South Line of Section
1,500 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Hodgeman
Lease Name: Fritzler Well #: 1-8
Date Well Completed: 4/16/08
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 3/3/09
Plugging Completed: 3/3/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	520'	none
		Production	4-1/2"	4284'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged hole w/125 sx 60/40 pozmix, 4% gel as follows: Pressured up on 4-1/2" casing annulus - full of cement. Pumped 25 sx cement through tubing @ 4174', 15 sx gel spacer @ 3737', 80 sx cement @ 1306', 20 sx to fill to surface.

KANSAS CORPORATION COMMISSION

APR 23 2009
RECEIVED

Plugging Contractor License #: 5663 Name: Hess Oil Company
Address 1: P. O. Box 1009 Address 2: _____
City: McPherson State: KS Zip: 67460 + 1009
Phone: (620) 241-4640
Name of Party Responsible for Plugging Fees: Hess Oil Company
State of KANSAS County, McPHERSON, ss.
Bryan Hess, President Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

Bryan Hess

4-21-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

JOB LOG

SWIFT Services, Inc.

DATE 03-23-09 PAGE NO. 1

CUSTOMER Mass Oil WELL NO. 18 LEASE FRITZER JOB TYPE PTD TICKET NO. 15378

CHART NO.	TIME	RATE (BPM)	VOLUME (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1245							ONLOCATION
								CMT 170 60-40PT 4% GEL
								200# HULLS, 15 SWS BENTONITE GEL
								2 7/8 x 4 1/2 TO 4325 POTO 4230, 8 5/8 @ 550 FT
								O.V. @ 1260
	1325		0.1		✓		300	PUS 8 5/8 FULL CMT
	1340	5.0	0	✓		100		1ST PUS TBL @ 4174, 25 SWS CMT 4/200# HULLS
	1340	5.0	7.0	✓		400		END CMT 1ST DISP 20 H2O, CIRC WATER
	1345	5.0	20.0	✓		600		END
								PULL 14 JOINTS, TBL @ 3740
	1405	4.0	0	✓		600		START GEL 15 SWS GEL
		4.0	2.0	✓		700		CIRC OIL, WATER
		4.0	46.0	✓		700		END GEL
	1420	4.0	2.0	✓		700		DEEP GEL
								PULL 78 JOINTS, TBL @ 1306
	1520	2.5	0	✓		0		START CMT
		2.5	6.0	✓		300		" TO CIRC
		2.5	20.0	✓		300		CIRC CMT
	1528	2.5	22.0	✓		300		END
								<u>80 SWS CMT</u>
								PULL TBL OUT
	1615		0	✓				TOP OFF 4 1/2
			4.0	✓				4 1/2 FULL 2 FT DOWN
								<u>20 SWS CMT</u>
	1630							WASH OUT TBL
								TOTAL CMT 125 SWS
								GEL 15 SWS
								HULLS 200 LBS
								JOB COMPLETE
								THANK YOU!
								DAVE, JOSH, SCOTT
								APR 23 2009
								RECEIVED
								KANSAS CORPORATION COMMISSION