

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-4
March 2009

Type or Print on this Form
Form must be Signed
All blanks must be Filled

WELL PLUGGING RECORD
K.A.R. 82-3-117

OPERATOR: License #: 05363
Name: Berexco, Inc.
Address 1: P.O. Box 723
Address 2: P O Box 20380 Wichita KS 67206
City: Hays State: KS Zip: 67601 +
Contact Person: Mark Lieker
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
3798 Depth to Top: 3805 Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - N/A 165-20088-0000
Spot Description: SE NE SW
Senesw Sec. 32 Twp. 16 S. R. 19 East West
3850 1649 Feet from North / South Line of Section
2310 3127 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rush
Lease Name: Ohnmacht Well #: 7
Date Well Completed: 12/67
The plugging proposal was approved on: 4/8/09 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 4/14/09
Plugging Completed: 4/14/09

KCC PER
DENIES

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
R Buckle	7'	Surface	8 5/8	147'	None
		Production	4 1/2	3798	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing was stuck, shot tubing off at 3775 pump down tubing, circ with annulus hole in tubing at 1280' back tubing off. Run tubing to 1227 circ cement to surface with 90 sacks 60/40 4% jell and 250# hulls. Pull tubing. Swedge onto 4 1/2 casing and pump 45 sacks 60/40 4% PSI to 500# and holding SHUT IN. Tie onto 8 5/8 pump 215 sacks 60/40 4% shut in.

RECEIVED
APR 23 2009
KCC WICHITA

Plugging Contractor License #: 5363 Name: Berexco, Inc.
Address 1: P.O. Box 723 Address 2: P O Box 20380 Wichita KS 67206
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, Inc.
State of Kansas County, Sedgwick, ss.
Mark Leiker Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Mark Leiker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]