

15-195-21811-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-21,811-00-00

LEASE NAME Walt

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 22 TWP. 11 RGE. 25 ~~28~~ or (W)

COUNTY Trego

LEASE OPERATOR Raymond Oil Co., Inc.

ADDRESS P.O. Box 58788 Wichita, KS 67201

PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5046

Date Well Completed 12-12-85

Character of Well D&A

Plugging Commenced 12-13-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS.  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4120

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|------|--------|------------|
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 2125' w/ 25 sacks 60/40 pozmix 6% gel thru drill pipe

Next Plug: @ 1205' w/100 sacks " " " " " " & 1 sack Hulls

Next Plug: @ 225' w/40 sacks " " " " " "

Top Plug: @ 40' w/Solid bridge of 1 sack Hulls & 10 cement 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney

(Employee of Operator) or ~~Operator~~ (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION  
Wichita, Kansas

(Signature) Bill Draney

12-18-1985  
DEC 18 1985

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

CONSERVATIVE  
Wichita, Kansas

Notary Public

My Commission Expires: 4-29-86

15-195-21811-00-00

DRILLER'S WELL LOG

DATE COMMENCED: December 6, 1985  
DATE COMPLETED: December 13, 1985

Raymond Oil Co., Inc.  
WALT #1  
NE SW NE  
Sec. 22, T11S, R25W  
Trego County, Ks.

ELEVATION: 2538 K.F.

0 - 2124' Surface Soil, Shale  
2124 - 2164' Anhydrite  
2164 - 3603' Shale & Lime  
3603 - 3607' Shale  
3607 - 3861' Lime & Shale  
3861 - 4099' Lime  
4099 - 4120' Shale & Lime  
4120' RTD

FORMATION DATA

Anhydrite 2124'  
Topeka 3603'  
Heebner 3825'  
Lansing K.C. 3861'  
Base K.C. 4099'  
RTD 4120'

Surface Pipe: Set new  
8-5/8", 203 pipe @216'  
w/140 sacks 60/40 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements  
herein are true and correct to the best of his knowledge.

*Bill Draney*

Subscribed and sworn to before me this 16 day of December 1985.

By Comm. Expires:

4-29-86

*Christy M. Haque*  
Notary Public

STATE OF KANSAS  
12-18-1985  
DEC 1 1985

NOTARY PUBLIC  
STATE OF KANSAS