

WELL PLUGGING RECORD

Give All Information Completely
Name Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Trego County, Sec. 33 Twp. 11 Rge. 25 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SW $\frac{1}{4}$ SE $\frac{1}{4}$

Lease Owner M. B. Armer

Lease Name Weissbeck Well No. 1

Office Address Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-20 1952

Application for plugging filed 1-20 1952

Application for plugging approved 1-20 1952

Plugging commenced 1-21 1952

Plugging completed 1-21 1952

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Eldon Petty

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	218	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 240', set plug and cemented with 15 Sacks cement. Filled hole to 40' with heavy drilling mud, set plug and cemented to bottom of cellar with 10 sacks cement.

2-1-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TRANSIT CORPORATION

Address 1516 Apco Tower, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma
L. J. Kruse (employee of ~~owner~~ or ~~owner's representative~~) Plugging Contractor of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. J. Kruse*

Oklahoma City, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 29th day of January, 1952

My commission expires October 24, 1955 *Lillian Wright* Notary Public.

33-1-230
141-7

H. B. ARMER

WELLSBORO # 1 WELL

SW/4 SW/4 SE/4
Sec. 33-11-29N
Dodge County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	80	2-5/8" C.S.A. @ 2 1/2". Cemented with 150 Bags Cement
Sand	80	100	
Shale	100	985	
Shale & Shells	985	1155	
Sand	1155	1480	
Sand, Shale Red Bed	1480	2028	
Lime & Shale	2028	2365	
Broken Lime & Shale	2365	2500	
Broken Lime Shale & Red Bed	2500	2703	
Lime & Shale	2703	3240	
Shale	3240	3293	
Lime & Shale	3293	3457	
Shale	3457	3554	
Lime & Shale	3554	3710	
Lime & Shale	3710	3810	
Lime	3810	3883	
Shale & Lime	3883	3937	
Lime	3937	4100	
Lime & Shale	4100	4250	
Shale & Lime	4250	4300	
Lime & Shale	4300	4345	
Lime	4345	4385	
Lime & Shale	4385	4435	
Tepped Miss. @ 4483'	4435	4500	
Lime & Chert	4500	4530	
Chert & Lime	4530	4550	
Massive Lime	4550	4580	
Cherty Lime	4580	4625	
Lime & Dolomite	4625	4661	
Lime	4661	4725	
Total Depth		4725'	

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

By: L. J. Kruse
 L. J. Kruse, Asst. Secretary

Subscribed and sworn to before me this 27th day of January, 1952.

My Commission Expires 2-1-1952
Sullivan Wright
 Notary Public

October 24, 1952

PLUGGING
 FILE SEC 33-11-29N
 PAGE 14 LINE 7