



STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
811 No. Broadway  
Wichita, Kansas

Trego County, Sec. 33 Twp. 11 Rge. 25 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Tom Palmer, Inc.  
Lease Name Weisbeck Well No. A-#1  
Office Address 1330 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-7-65 19  
Application for plugging filed 2-7-65 19  
Application for plugging approved 2-7-65 19  
Plugging commenced 2-7-65 19  
Plugging completed 2-7-65 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4500 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251.43'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 550' with 20 sacks cement  
Plug @ 240' with 20 sacks cement  
Plug @ 40' with 10 sacks cement 1/2 sack hulls

RECEIVED  
STATE CORPORATION COMMISSION  
2-11-1965  
FEB 11 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of February, 1965

Wanda Nichols  
Notary Public.

My Commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Tom Palmer, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: WEISBECK A-#1  
 LOCATION: C NE NE Sec. 33-11S-25W  
 TREGO COUNTY, KANSAS  
 COMMENCED: 1-29-65  
 COMPLETED: 2-7-65

0	105	Shale & Sand
105	125	Water & Sand
125	200	Sand & Shale
200	252	Shale
252	2131	Shale & Shells
2131	2177	Anhydrite
2177	2600	Shale
2600	3846	Lime & Shale
3846	4500	Lime
	<u>4500</u>	<u>Rotary Total Depth - D. &amp; A.</u>

2-11-1965  
 FEB 11 1965  
 NOTARY PUBLIC  
 WANDA NICHOLS

Set 8 5/8" casing @ 251.43' cemented with 175 sacks Posmix #1, 9% Gel HA5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Weisbeck A-#1 well, located C NE NE of Section 33, Township 11 South, Range 25 West, Trego County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS }  
 COUNTY OF BARTON } SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 10th day of February, 1965.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires  
 April 1, 1967