

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

6-14-79

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1979
CONSERVATION DIVISION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name R.P. NIXON OPERATIONS

Complete Address 207 WEST 12TH STREET HAYS, KANSAS

Lease Name NELSON Well No. #1

Location SE-SE-NE Sec 34 Twp. 10 Rge. 16 (E) (W) W

County ROOKS Total Depth ~~3380~~ 3380'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor KELSO CASING BULLING

Address BOX 176 CHASE MS License No. 683

Operation Completed: Hour 10:30 AM Day 12 Month JUNE Year 1979

The above well was plugged as follows: 3380'

8 5/8 228' SP. CUC 205ST - 4 1/2 ~~3380~~ CUC 175ST - PERFS. 3212' to 3215'

SET PLUG. AT 3000' SHOT PIPE AT 2500' RECOVERED 2413'

BOTTOM SANDED TO 2900' AND 5ST CMT.

ORDERED 140ST 50/50 PZMIX 6% GEL - 16ST GEL. - 1ST HULLS.

PUMPED IN 12ST GEL - 70ST CMT - 4ST GEL - 1ST HULLS

RELEASED PLUG AND 70ST CMT.

MAX. PRESSURE BUILT UP 300^{PSI} SHUT DOWN 0^{PSI}

ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Marion Schmidt
Well Plugging Supervisor

DATE 6-15-79

INV. NO. 9832-W