

15-163-19394-0001

KANSAS

Form CP-3  
Rev. 6-4-68STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTRECEIVED  
STATE CORPORATION COMMISSION  
12-26-72  
DEC 26 1972J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Theresa D. Nixon

Complete Address Box 589 Russell, Kansas 67665

Lease Name Nelson Well No. 2

Location SW SE NE Sec. 34 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3530'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Comstock Pipe Pulling

Address Stafford, Kansas 67578 License No. 490

Operation Completed: Hour 11:30 A Day 22 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3540' 10 3/4 csg set at 130' CWC.

5 1/2 csg set at 3528' cw 100 sk cmt.

5 1/2 csg PBTB 3270' with top perf. (3160)

Set 5 1/2 wood plug at 3100' -poured 25' sd -dumped 5 sk cmt W/dump bailer. (3040-3100)

Cutoff and recovered 2647' of 5 1/2 csg.

Pumped down 10 3/4 csg with 25 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk gel & water -released 10 3/4 plug and pumped 70 sk cmt. PP 250 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mueser  
Well Plugging SupervisorDATE: 12/26/72  
INV. NO. 6771-W