

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 83-29

LOCATION SW SE NE

SEC. 34 TWP. 10RGE. 16

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Nelson

Operator Lohmann & Johnson Address 320 Indiana Bk Bldg

Field _____ County Evansville, Ind
Rooks

Total Depth 3530 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 300' circulated with cement - 5 1/2" at 3529' (with

200 sax cement behind - P. B. to 3240', perforated at 3162',

Filled with sand to 3150', set 4 sax cement with dump bailer,

pulled 2510' 5 1/2" - filled with mud to 300', set rock and

20 sax cement, mud to 30', set rock and 10 sax cement to

bottom cellar.

District Conservation Agent

Date 7-30-56

PLUGGING
FILE SEC 34 T 10 R 16W
BOOK PAGE 83 LINE 29

8-7-56

CONSERVATION DIVISION
WICHITA, KANSAS