

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

1-20-77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name K. R. M.

Complete Address Box 298, Little River, Kansas 67457

Lease Name O'Leary "A" Well No. 2

Location SW NE SE Sec. 34 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3568'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Keaso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 19 Month 1 Year 1977

The above well was plugged as follows:

Total Depth 3568' 8 5/8 csg set 230' cwc 150 sx.

5 1/2 csg set 3566' cw 100 sx cem.

5 1/2 csg FBTD 3500' with top perf. (3232')

Set 5 1/2 wood plug at 3100' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3100'-3060')

Cutoff & recovered 2000' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water W/300

lbs hulls, 50 sk "Comm 4%", displaced with 10 sk gel & water, released 8 5/8 plug

& capped with 50 sk "Comm 4% & shutin. MPP 350 lbs. SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 1-20-77

INV. NO. 4508-4