



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
8-15-74
AUG 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co., Inc.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Post-Conger Well No. 3

Location SW SE NE Sec. 16 Twp. 10 Rge. (E) (W) 16

County Rooks Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 3:30 A Day 13 Month 8 Year 1974

The above well was plugged as follows:

- RTD 3630' 8 5/8 csg set at 252' cwt: 200 sk. Cmt. Mat. 50-50 poz 6% total gel.
- Gunned pits, circulated heavy mud, displaced 50 sk cmt at 500' thru drill pipe.
- Heavy mud to 240' set cementing plug and displaced 25 sk cmt thru drill pipe.
- Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey
Well Plugging Supervisor

INVOICED

DATE 8/15/74
INV. NO. 9710-W